



# Hall County Government FIRE SERVICES

PO BOX 907730  
GAINESVILLE, GA 30501  
t: 770-531-6838 – f: 770-531-6845  
[www.hallcountymfire.org](http://www.hallcountymfire.org)

Fire Chief  
Chris  
Armstrong



## **Project Check List**

**Below are some items that will be required while the building process is taking place:**

1. A water main with hydrants spacing as necessary to facilitate a 400-foot lay of fire hose to any portion of all buildings. This distance is measured 'as the truck travels'. All fire hydrants shall be capable of providing a minimum flow of 1250 gallons per minute.
2. Hydrants and mains shall be installed and under pressure before any combustible construction is started.
3. Certification and flow tests shall be provided to the Fire Department after installation of the water mains.
4. Every building hereafter constructed shall be accessible to fire department vehicles.
5. Maintain access for emergency vehicles around and to all buildings under construction. i.e.: In times of rain or mud, roads shall be capable of carrying the weight of a fire truck by being paved or having a crushed stone base etc. This emergency access shall be a minimum of 20 feet wide (International Fire Code 2012).
6. Any blasting/explosive operations must first be permitted through Hall County Fire Marshal's Office.

\*All burning of land clearing debris must be done according to Hall County Fire Services and EPD regulations.

**If you have any questions, please email the Fire Marshal's Office at [FireReview@hallcounty.org](mailto:FireReview@hallcounty.org).**